



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County George
Project No. SAP-20(12)M
Road Name. Basin-Bexley Road (River Road)

BIDS RECEIVED: TUESDAY, APRIL 7, 2026 AT 10:00 AM IN THE BOARDROOM AT LUCEDALE, MS

Project Description: 4.206 miles of OVERLAY

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CRUSHED STONE (SIZE 825B)	1,755.000	TON
3" IN-GRADE PREPARATION	8.400	MI
HOT MIX ASPHALT, (ST), (9.5 mm MIXTURE), BASE REPAIRS	1.000	TON
HOT MIX ASPHALT,(ST), (9.5 mm MIXTURE), OVERLAY	4,112.000	TON
HOT MIX ASPHALT, (ST), (9.5 mm MIXTURE)	375.000	TON
HOT MIX ASPHALT, (ST), (9.5 mm MIXTURE), LEVELING	338.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	820.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE TEMPORARY TRAFFIC STRIPE	9,561.000	LF
4" WIDE TEMPORARY TRAFFIC STRIPE	32,982.000	LF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	8.415	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	1.811	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	6.247	MI
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	495.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	100.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	563.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	4.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	8.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	8.000	EA