



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** George  
**Project No.** SAP-20(13)M  
**Road Name.** Cooks Corner Road

**BIDS RECEIVED:** TUESDAY, APRIL 7, 2026 AT 10:00 AM IN THE BOARDROOM AT LUCEDALE, MS

**Project Description:** 2.135 miles of OVERLAY

**ROADWAY ITEMS:**

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	4.000	CY
CRUSHED STONE (SIZE 825 B)	739.000	TON
ASPHALT, ST, 9.5 mm	1,990.000	TON
ASPHALT, ST, 9.5 mm	216.000	TON
ASPHALT, ST, 9.5 mm, LEVELING	1,195.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	391.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE TEMPORARY TRAFFIC STRIPE	13,071.000	LF
4 " WIDE TEMPORARY TRAFFIC STRIPE	27,941.000	LF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	4.303	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	1.238	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	2.684	MI
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	540.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	80.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	282.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	5.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	5.000	EA