



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County George
Project No. SAP 20(16)S
Road Name. Brushy Creek Road

BIDS RECEIVED: TUESDAY, APRIL 7, 2026 AT 10:00 AM IN THE BOARDROOM AT LUCEDALE, MS

Project Description: 3.913 miles of RESEAL (MICRO-SURFACING)

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	10.000	CY
CRUSHED STONE (SIZE 610)	275.000	TON
ASPHALT, (ST) (9.5 mm)	34.000	TON
ASPHALT, (ST) (4.75 mm), LEVELING	848.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	1,731.000	SY
EMULSIFIED ASPHALT FOR MICRO-SURFACING	16,210.000	GAL
AGGREGATE FOR MICRO SURFACING (TYPE II)	486.000	TON
SCRUB SEAL	48,699.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4"- WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) ([60 MILS])	7.989	MI
4"- WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) ([90 MILS])	1.686	MI
4"- WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) ([90 MIL])	6.008	MI
THERMOPLASTIC LEGEND (WHITE) ([120 MILS])	1,080.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH-PERFORMANCE RAISED MARKERS	180.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	524.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	17.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	9.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (Type 3)	4.000	EA