



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Hancock

Project No. SAP-23(14)M

Road Name. ROADS "A" - "B"

BIDS RECEIVED: Monday, October 19, 2026 10:00 am in the Boardroom at Bay St. Louis, MS

Project Description: 11.819 miles of MAINTENANCE (OTHER THAN BRIDGE)

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	130.000	CY
Granular Material (LVM) (Class 5, Group C)	200.000	CY
Asphalt, ST, 9.5mm	1,444.000	TON
Asphalt, ST, 9.5mm, (Base Repair)	257.000	TON
Cold Milling of Bituminous Pavement, All Depths	13,126.000	SY
Emulsified Asphalt for Micro-Surfacing	59,871.000	GAL
Aggregate for Micro-Surfacing (Type III)	1,871.000	TON
Scrub Seal	149,676.000	SY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mil)	24.093	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 Mil)	4.262	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mil)	18.759	MI
Thermoplastic Detail Stripe (4" Equivalent Length) (White) (60 Mil)	413.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (Yellow) (90 Mil)	206.000	LF
Thermoplastic Legend (White) (120 Mil)	580.000	SF
Two-Way Yellow Reflective High-Performance Raised Markers	1,561.000	EA