



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Jefferson Davis
Project No.	SAP-33(23)M
Road Name.	Sonat Road

BIDS RECEIVED: TUESDAY, MARCH 10, 2026 AT 10:00 AM IN THE BOARDROOM AT PRENTISS, MS

Project Description: 0.082 miles of MAINTENANCE (OTHER THAN BRIDGE) Pipe Replacement

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PIPE (ALL SIZES)	130.000	LF
UNCLASSIFIED EXCAVATION (FM)	165.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	220.000	CY
STRUCTURE EXCAVATION	170.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	60.000	CY
CRUSHED STONE, 610	300.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	60.000	CY
HOT MIX ASPHALT, ST 9.5 MM	75.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	500.000	SY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.558	CY
48" REINFORCED CONCRETE PIPE, CLASS III	72.000	LF
48" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
51" X 31" REINFORCED CONCRETE ARCH PIPE, CLASS III	72.000	LF
51" X 31" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.094	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	500.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	8.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.600	TON
COMMERCIAL FERTILIZER (13-13-13)	0.300	TON
SEEDING	0.300	AC
VEGETATIVE MATERIALS FOR MULCH	0.600	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	375.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 200 LB.	130.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	260.000	SY

ADD OPTION NO. 1 ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PIPE (ALL SIZES)	110.000	LF
UNCLASSIFIED EXCAVATION (FM)	300.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	230.000	CY
STRUCTURE EXCAVATION	310.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	25.000	CY
CRUSHED STONE, 610	250.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	75.000	CY
HOT MIX ASPHALT, ST 9.5 MM	37.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	200.000	SY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	25.560	CY
REINFORCING STEEL	1,482.000	LB
60" REINFORCED CONCRETE PIPE, CLASS III	144.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.038	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	200.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	3.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	1.000	EA
AGRICULTURAL LIMESTONE	0.200	TON
COMMERCIAL FERTILIZER (13-13-13)	0.100	TON
SEEDING	0.100	AC
VEGETATIVE MATERIALS FOR MULCH	0.200	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	300.000	LF
WATTLES, 20"	80.000	LF
LOOSE RIPRAP, 200 LB.	110.000	TON
GROUTED RIPRAP	100.000	SY
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	220.000	SY

ADD OPTION NO. 2 ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PIPE (ALL SIZES)	72.000	LF
UNCLASSIFIED EXCAVATION (FM)	300.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	95.000	CY
STRUCTURE EXCAVATION	275.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	25.000	CY
CRUSHED STONE, 610	300.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	100.000	CY
HOT MIX ASPHALT, ST 9.5 MM	37.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	200.000	SY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	63.720	CY
REINFORCING STEEL	2,584.000	LB
72" REINFORCED CONCRETE PIPE, CLASS III	144.000	LF

RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.038	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	200.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	3.000	EA
AGRICULTURAL LIMESTONE	0.200	TON
COMMERCIAL FERTILIZER (13-13-13)	0.100	TON
SEEDING	0.100	AC
VEGETATIVE MATERIALS FOR MULCH	0.200	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	250.000	LF
WATTLES, 20"	80.000	LF
LOOSE RIPRAP, 200 LB.	60.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	120.000	SY