



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Jefferson Davis

Project No. SAP-33(24)M

Road Name. NORTH WILLIAMSBURG ROAD

BIDS RECEIVED: MONDAY, NOVEMBER 17, 2025 AT 10:00 AM IN THE BOARDROOM AT PRENTISS, MS

Project Description: 6.013 miles of MAINTENANCE (OTHER THAN BRIDGE) OVERLAY

ROADWAY ITEMS:

Mobilization	1.000	LS
Granular Material LVM, (Class 6, Group C)	530.000	CY
Asphalt, Type ST, Mixture 9.5 mm, (Edge Repair)	18.000	TON
Cold Milling of Bituminous Pavement, All Depths	389.000	SY
Ultra-Thin Asphalt Pavement	1,283.000	TON
Ultra-Thin Asphalt Pavement	227.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	3.590	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mils)	0.375	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	16,974.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	175.000	EA