



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

|                    |                 |
|--------------------|-----------------|
| <b>County</b>      | Jefferson Davis |
| <b>Project No.</b> | SAP-33(25)M     |
| <b>Road Name.</b>  | Old River Road  |

**BIDS RECEIVED:** Monday, December 15, 2025 at 10:00 am in the Boardroom at Prentiss, MS

**Project Description:** 0.261 miles of MAINTENANCE (OTHER THAN BRIDGE)

**ROADWAY ITEMS:**

|                                                                    |           |     |
|--------------------------------------------------------------------|-----------|-----|
| Mobilization                                                       | 1.000     | LS  |
| Granular Material LVM, (Class 6, Group C)                          | 25.000    | CY  |
| Polymerized Emulsified Asphalt, Grade CRS-2P                       | 3,330.000 | GAL |
| Seal Aggregate Cover Material, Size 5, Type Crused Stone           | 72.000    | CY  |
| Seal Aggregate Cover Material, Size 7, Type Crushed Stone          | 37.000    | CY  |
| Blotter Material                                                   | 13.000    | CY  |
| Maintenance of Traffic                                             | 1.000     | LS  |
| Additional Construction Signs                                      | 0.000     | SF  |
| 4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)     | 0.606     | MI  |
| 4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils) | 3,200.000 | LF  |
| Two-Way Yellow Reflective High-Performance Raised Markers          | 40.000    | EA  |
| Reflectorized Traffic Warning Sign (Encapsulated Lens)             | 2.000     | EA  |
| Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)   | 4.000     | EA  |
| Roadbed Reclamation                                                | 3,884.000 | SY  |