



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Jefferson Davis

Project No. SAP-33(26)M

Road Name. Roads "A" Thru "B"

BIDS RECEIVED: THURSDAY, MARCH 26, 2026 AT 10:00 AM IN THE BOARDROOM AT PRENTISS, MS

Project Description: 8.308 miles of MAINTENANCE (OTHER THAN BRIDGE)

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	27.000	CY
Granular Material LVM, (Class 6, Group C)	83.000	CY
Asphalt, Type ST, Mixture 9.5 mm, (Base Repair & Edge Repair)	136.000	TON
Asphalt, Type ST, Mixture 9.5 mm, Leveling	412.000	TON
Cold Milling of Bituminous Pavement, All Depths	100.000	SY
Polymerized Emulsified Asphalt, Grade CRS-2P	45,321.000	GAL
Seal Aggregate Cover Material, Size 7, Type Crushed Stone or Slag	1,119.000	CY
Blotter Material	160.000	CY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) 60 mils)	16.543	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	88,168.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (White) (60 mils)	1,590.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (Yellow) (90 mils)	380.000	LF
Thermoplastic Legend (White) (120 mils)	360.000	LF
Thermoplastic Legend (White) (120 mils)	444.000	SF
Two-Way Clear Reflective High-Performance Raised Markers	495.000	EA
Two-Way Yellow Reflective High-Performance Raised Markers	805.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	95.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	17.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	20.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	8.000	EA

ADD OPTION NO. 1 ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Maintenance of Traffic	1.000	LS
Asphalt for Fog Seal, Grade LD-7 or CHPF-1	11,870.000	GAL