



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Kemper
Project No. SAP-35(14)S
Road Name. ROADS "A" THROUGH "C"

BIDS RECEIVED: FRIDAY, JUNE 26, 2026 AT 10:00 AM IN THE SUPERVISOR'S ANNEX AT DE KALB, MS

Project Description: 11.855 miles of RESEAL

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (F.M.)	182.000	CY
Asphalt, ST, 12.5 mm, Base Repair	360.000	TON
Asphalt, ST, 12.5 mm, Edge Repair	60.000	TON
Asphalt, ST, 12.5 mm, Leveling	443.000	TON
Polymerized Emulsified Asphalt, Grade CRS-2P	63,112.000	GAL
Seal Aggregate Cover Material, Size 7, Type Crushed Stone	1,647.000	CY
Blotter Material	213.000	CY
Fog Seal Mixture	15,778.000	GAL
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (90 MIL)	23.530	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 MIL)	5.512	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 MIL)	88,899.000	LF
Thermoplastic Legend (White) (120 MIL)	954.000	LF
Two-Way Clear Reflective High-Performance Raised Markers	286.000	EA
Two-Way Yellow Reflective High-Performance Raised Markers	920.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	90.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	18.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA