



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Kemper  
**Project No.** SAP-35(77)  
**Road Name.** Old Jackson Road

**BIDS RECEIVED:** Wednesday, September 30, 2026 at 10:00 am at the Supervisor's Annex at DeKalb, MS

**Project Description:** 0.179 miles of BRIDGE and APPROACHES

**ROADWAY ITEMS:**

|                                                                    | QUANTITY  | UNIT |
|--------------------------------------------------------------------|-----------|------|
| Mobilization                                                       | 1.000     | LS   |
| Clearing and Grubbing                                              | 1.000     | LS   |
| Removal of Bridge at Sta. 20+17.00                                 | 1.000     | UN   |
| Removal of Bridge at Sta. 26+83.00                                 | 1.000     | UN   |
| Removal of Pipe (All Sizes)                                        | 17.000    | LF   |
| Unclassified Excavation (FM)                                       | 347.000   | CY   |
| Borrow Excavation (Contractor-Furnished FME, Class 9)              | 788.000   | CY   |
| Granular Material (LVM) (Class 9, Group B)                         | 583.000   | CY   |
| Crushed Stone (Size 610) (LVM)                                     | 134.000   | CY   |
| Asphalt, ST, 12.5 mm                                               | 139.000   | TON  |
| Asphalt, ST, 19 mm                                                 | 275.000   | TON  |
| 18" Reinforced Concrete Pipe, Class III                            | 24.000    | LF   |
| Guardrail, W-Beam                                                  | 150.000   | LF   |
| Guardrail, Bridge End Section, Type "I" Thrie-Beam                 | 8.000     | EA   |
| Guardrail, Terminal End Section                                    | 8.000     | EA   |
| Maintenance of Traffic                                             | 1.000     | LS   |
| Additional Construction Signs                                      | 0.000     | SF   |
| 4" Wide Thermoplastic Edge Stripe (Continuous White) (90 MIL)      | 0.359     | MI   |
| 4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 MIL) | 1,900.000 | LF   |
| Two-Way Yellow Reflective High Performance Raised Markers          | 12.000    | EA   |
| Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)   | 8.000     | EA   |

**EROSION CONTROL ITEMS:**

|                                                | QUANTITY  | UNIT |
|------------------------------------------------|-----------|------|
| Solid Sodding                                  | 248.000   | SY   |
| Excelsior Blanket                              | 750.000   | SY   |
| Hydroseeding, Temporary Grassing               | 0.930     | AC   |
| Temporary Silt Fence (Type II) (AOS 0.15-0.84) | 1,500.000 | LF   |
| Wattles, 20"                                   | 250.000   | LF   |
| Loose Riprap (200 LB.)                         | 200.000   | TON  |

**BRIDGE A ITEMS:**

|                                      | QUANTITY | UNIT |
|--------------------------------------|----------|------|
| Test Pile, 14", Prestressed Concrete | 2.000    | EA   |
| Conventional Static Pile Load Test   | 0.000    | EA   |
| 14" Prestressed Concrete Piling      | 590.000  | LF   |

|                                                            |         |     |
|------------------------------------------------------------|---------|-----|
| 18" Pre-formed Pile Holes                                  | 400.000 | LF  |
| 19' Precast Concrete Slab Unit, 3.5' Interior              | 18.000  | EA  |
| 19' Precast Concrete Slab Unit, 3.5' Exterior              | 6.000   | EA  |
| Precast Concrete Barrier Rail                              | 114.000 | LF  |
| 31' Precast Concrete Cap, Intermediate Unit, Concrete Pile | 2.000   | EA  |
| 31' Precast Concrete Cap, End Unit, Concrete Pile          | 2.000   | EA  |
| 9.25' Precast Concrete Wing                                | 4.000   | EA  |
| Loose Riprap (300 LB.)                                     | 230.000 | TON |
| Geotextile Under Riprap, Non-Woven (Type V) (AOS < 0.43)   | 252.000 | SY  |

**BRIDGE B ITEMS:**

|                                                            | QUANTITY | UNIT |
|------------------------------------------------------------|----------|------|
| Test Pile, 14", Prestressed Concrete                       | 2.000    | EA   |
| Conventional Static Pile Load Test                         | 0.000    | EA   |
| 14" Prestressed Concrete Piling                            | 590.000  | LF   |
| 18" Pre-formed Pile Holes                                  | 400.000  | LF   |
| 19' Precast Concrete Slab Unit, 3.5' Interior              | 18.000   | EA   |
| 19' Precast Concrete Slab Unit, 3.5' Exterior              | 6.000    | EA   |
| Precast Concrete Barrier Rail                              | 114.000  | LF   |
| 31' Precast Concrete Cap, Intermediate Unit, Concrete Pile | 2.000    | EA   |
| 31' Precast Concrete Cap, End Unit, Concrete Pile          | 2.000    | EA   |
| 9.25' Precast Concrete Wing                                | 4.000    | EA   |
| Loose Riprap (300 LB.)                                     | 230.000  | TON  |
| Geotextile Under Riprap, Non-Woven (Type V) (AOS < 0.43)   | 252.000  | SY   |