OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Lafayette
Project No. SAP-36(84)
Road Name. CARD ROAD (C.R. 459)

BIDS RECEIVED: TUESDAY, DECEMBER 15, 2026 AT 9:00 AM IN THE BOARDROOM AT OXFORD, MS
Project Description: 0.095 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (STA. 111+ 89)	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	34.000	LF
REMOVE AND RELAY RIPRAP	55.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,012.000	CY
EXCESS EXCAVATION (FM)	178.000	CY
STRUCTURE EXCAVATION	750.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE III) (AOS < 0.43 mm)	500.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL, (CLASS 4, GROUP "C")	142.000	TON
CRUSHED STONE (SIZE 57)	332.000	TON
CRUSHED STONE (SIZE 610)	924.000	TON
MIXING, SHAPING AND COMPACTION	1,219.000	SY
HOT MIX ASPHALT, ST, _9.5 mm	92.000	TON
HOT MIX ASPHALT, ST, 12.5 mm	92.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.166	CY
13 1/2" X 22" REINFORCED CONCRETE ARCH PIPE,CLASS III	40.000	LF
18" X 28 1/2" REINFORCED CONCRETE ARCH PIPE,CLASS III	48.000	LF
18" X 28 1/2" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	11.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.191	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	1,010.000	LF
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	2.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.800	TON
AMMONIUM NITRATE	0.080	TON
SEEDING	0.800	AC
VEGETATIVE MATERIALS FOR MULCH	2.400	TON
EXCELSIOR BLANKET	550.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	400.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	590.000	TON

GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43 mm	140.000	SY
BOX BRIDGE ITEMS:		
BOX BRIDGE CONCRETE, CLASS "BB"	309.293	CY
REINFORCEMENT	60,301.000	LB