



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

|                    |                 |
|--------------------|-----------------|
| <b>County</b>      | Lamar           |
| <b>Project No.</b> | SAP-37(18)M     |
| <b>Road Name.</b>  | Roads "A" - "C" |

**BIDS RECEIVED:** FRIDAY, AUGUST 1, 2025 AT 10:00 AM IN THE BOARDROOM AT PURVIS, MS

**Project Description:** 12.832 miles of OVERLAY

**ROADWAY ITEMS:**

|                                                                        |             |     |
|------------------------------------------------------------------------|-------------|-----|
| MOBILIZATION                                                           | 1.000       | LS  |
| REMOVAL OF EXISTING TRAFFIC STRIPE                                     | 1,532.000   | LF  |
| REMOVAL OF PIPE (ALL SIZES)                                            | 66.000      | LF  |
| UNCLASSIFIED EXCAVATION (FM)                                           | 235.000     | CY  |
| STRUCTURE EXCAVATION                                                   | 31.000      | CY  |
| GRANULAR MATERIAL (LVM), (CLASS 5, GROUP B)                            | 3,100.000   | CY  |
| CRUSHED STONE (610)                                                    | 274.000     | TON |
| HOT MIX ASPHALT, (ST) (9.5 mm)                                         | 14,796.000  | TON |
| HOT MIX ASPHALT, (ST) (9.5 mm) (BASE REPAIR)                           | 1,986.000   | TON |
| HOT MIX ASPHALT, (ST) (12.5 mm) (BASE REPAIR)                          | 229.000     | TON |
| HOT MIX ASPHALT, (ST) (9.5mm) (EDGE REPAIR)                            | 128.000     | TON |
| COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS                        | 22,013.000  | SY  |
| ASPHALT FOR TACK COAT                                                  | 2,333.000   | GAL |
| ULTRA THIN ASPHALT PAVEMENT                                            | 2,564.000   | TON |
| CLEANING AND SEALING CRACKS                                            | 21,000.000  | LF  |
| CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES                        | 0.330       | CY  |
| 30" REINFORCED CONCRETE PIPE, CLASS III                                | 32.000      | LF  |
| 30" REINFORCED CONCRETE PIPE, END SECTION                              | 2.000       | EA  |
| 22" X 13" REINFORCED CONCRETE ARCH PIPE, CLASS III                     | 24.000      | LF  |
| 22" X 13" REINFORCED CONCRETE ARCH PIPE, END SECTION                   | 2.000       | EA  |
| MAINTENANCE OF TRAFFIC                                                 | 1.000       | LS  |
| ADDITIONAL CONSTRUCTION SIGNS                                          | 0.000       | SF  |
| 4" WIDE COLD PLASTIC EDGE STRIPE (CONTINUOUS WHITE)                    | 0.145       | MI  |
| 4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)                | 766.000     | LF  |
| 4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)         | 25.316      | MI  |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)           | 0.740       | MI  |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)     | 130,715.000 | LF  |
| THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) (60 MILS)  | 4,428.000   | LF  |
| THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) (90 MILS) | 1,674.000   | LF  |
| THERMOPLASTIC LEGEND (WHITE) (120 MILS)                                | 2,228.000   | LF  |
| TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS               | 1,674.000   | EA  |
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS              | 1,270.000   | EA  |
| REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)                 | 128.000     | EA  |
| REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)              | 41.000      | EA  |

|                                                                            |        |     |
|----------------------------------------------------------------------------|--------|-----|
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)           | 32.000 | EA  |
| REFLECTORIZED TRAFFIC REGULATORY SIGN WITH SUPP. PLATE (ENCAPSULATED LENS) | 6.000  | EA  |
| LOOSE RIPRAP, 200 LB.                                                      | 9.000  | TON |

**EROSION CONTROL ITEMS:**

|                                                |         |     |
|------------------------------------------------|---------|-----|
| AGRICULTURAL LIMESTONE                         | 25.000  | TON |
| COMMERCIAL FERTILIZER (13-13-13)               | 12.000  | TON |
| AMMONIUM NITRATE                               | 1.230   | TON |
| SEEDING                                        | 12.000  | AC  |
| VEGETATIVE MATERIALS FOR MULCH                 | 25.000  | TON |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84) | 250.000 | LF  |
| WATTLES, 20"                                   | 120.000 | LF  |