



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Leflore
Project No. SAP-42(67)
Road Name. COUNTY ROAD 512

BIDS RECEIVED: MONDAY, OCTOBER 27, 2025 AT 3:00 PM IN THE BOARDROOM AT GREENWOOD, MS
Project Description: 0.04 miles of BOX CULVERT & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 30+71.50	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	442.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	945.000	CY
CHANNEL EXCAVATION (FM)	395.000	CY
STRUCTURE EXCAVATION	335.000	CY
GEOTEXTILE FABRIC STABILIZATION, TYPE V, NON-WOVEN	872.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE, SIZE 57	225.000	TON
CRUSHED STONE, SIZE 610	537.000	TON
HOT MIX ASPHALT, ST, 12.5MM	78.000	TON
CLASS "B" STRUCTURAL CONCRETE	157.070	CY
REINFORCING STEEL	30,337.000	LB
CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.040	TON
COMMERCIAL FERTILIZER (13:13:13)	0.520	TON
AMMONIUM NITRATE	0.050	TON
SEEDING	0.520	AC
VEGETATIVE MATERIALS FOR MULCH	1.560	TON
EXCELSIOR BLANKET	155.000	SY
TEMPORARY SILT FENCE, TYPE II, AOS 0.15-0.84	500.000	LF
WATTLES, 12"	150.000	LF
LOOSE RIPRAP, 300 LB.	390.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	1,020.000	SY