



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Leflore
Project No. SAP-42(69)
Road Name. CR 547

BIDS RECEIVED: MONDAY, DECEMBER 7, 2026 AT 3:00 PM IN THE BOARDROOM AT GREENWOOD, MS
Project Description: 0.181 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 6+50	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	80.000	LF
UNCLASSIFIED EXCAVATION (F.M.)	3,018.000	CY
EXCESS EXCAVATION (F.M.)	643.000	CY
GRANULAR MATERIAL (LVM), (CL. 4, GP.B)	1,898.000	CY
48" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
GUARD RAIL, W-BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I"(THRIE BEAM)	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.700	TON
COMMERCIAL FERTILIZER (13:13:13)	1.850	TON
AMMONIUM NITRATE	0.190	TON
SEEDING	1.850	AC
VEGETATIVE MATERIALS FOR MULCH	3.700	TON
SOLID SODDING	800.000	SY
EXCELSIOR BLANKET	335.000	SY
TEMPORARY SILT FENCE	700.000	LF
WATTLES, 12"	300.000	LF
LOOSE RIPRAP(300 LB.)	1,625.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	3,025.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	2,340.000	LF
24" PRE-FORMED PILE HOLE	950.000	LF
BRIDGE CONCRETE, CLASS "A"	146.190	CY

31' PRESTRESSED CONCRETE BEAM (TYPE I + 2)	307.500	LF
40' PRESTRESSED CONCRETE BEAM (TYPE I + 2)	198.750	LF
REINFORCEMENT	25,492.000	LB
CONCRETE RAILING	204.000	LF
LOOSE RIPRAP (300 LB.)	620.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	1,160.000	SY
<u>RAILWAY</u>		
RAILWAY-FLAGGING	1.000	LS