



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Lincoln

Project No. SAP-43(17)M

Road Name. Roads "A" thru "I"

BIDS RECEIVED: MONDAY, MAY 11, 2026 AT 10:00 AM IN THE BOARDROOM AT BROOKHAVEN, MS

Project Description: 27.157 miles of MAINTENANCE (OTHER THAN BRIDGE)

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Headwall	4.000	UN
Removal of Pipe (All Sizes)	242.000	LF
Unclassified Excavation, (FM)	2,416.000	CY
Borrow Excavation (Contractor Furnished, LVM Class 7)	1,200.000	CY
Excess Excavation (FM)	600.000	CY
Granular Material (LVM), (Class 6, Group C)	200.000	CY
Asphalt, ST 9.5 mm (Surface Course)	158.000	TON
Asphalt, ST 19 mm (Base Course)	141.000	TON
Asphalt, ST 19mm (Base Repair)	675.000	TON
Asphalt, ST 9.5 mm, Leveling	12,729.000	TON
Polymerized-Emulsified Asphalt, Grade CRS-2P	94,728.000	GAL
Seal Aggregate Cover Material, Size 7, Crushed Stone or Slag	2,339.000	CY
Class "B" Structural Concrete, Minor Structures	1.268	CY
72" Reinforced Concrete Pipe, Class III	48.000	LF
72" Reinforced Concrete Pipe, End Section	2.000	EA
44" x 27" Reinforced Concrete Arch Pipe, Class III	48.000	LF
65" x 40" Reinforced Concrete Arch Pipe, Class III	48.000	LF
73" x 45" Reinforced Concrete Arch Pipe, Class III	40.000	LF
44" x 27" Reinforced Concrete Arch Pipe, End Section	2.000	EA
65" x 40" Reinforced Concrete Arch Pipe, End Section	2.000	EA
73" x 45" Reinforced Concrete Arch Pipe, End Section	2.000	EA
Filter Material for Filter Beds, Type A	200.000	CY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 Mil)	36.207	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 Mil)	9.442	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mil)	132,488.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (White) (90 Mil)	4,800.000	LF
Thermoplastic Legend (White) (120 mil)	2,667.000	LF
Thermoplastic Legend (White) (120 mil)	125.000	SF
Two-Way Clear Reflective High Performance Raised Markers	1,100.000	EA
Two-Way Yellow Reflective High Performance Raised Markers	1,677.000	EA

Reflectorized Traffic Warning Sign (Encapsulated Lens)	97.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	34.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	64.000	EA
Reflectorized Advance Warning Sign (Encapsulated Lens)	2.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	5.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Commercial Fertilizer (13-13-13)	1.000	TON
Seeding	1.000	AC
Vegetative Materials for Mulch	3.000	TON
Solid Sodding	1,000.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	400.000	LF
Erosion Mat	75.000	SY
Wattles, 20"	200.000	LF
Loose Riprap, 300 Lb.	50.000	TON
Geotextile Under Loose Riprap, Type V, AOS < 0.43, Non-Woven	40.000	SY