



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Lowndes
Project No.	SAP-44(15)M
Road Name.	Roads "A" - "D"

BIDS RECEIVED: Tuesday October 21, 2025 at 10:00 am at the Supervisors Boardroom at Columbus Ms

Project Description: 8.446 miles of OVERLAY

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	1,541.000	CY
GRANULAR MATERIAL (LVM) (CLASS 3, GROUP "B")	3,302.000	CY
HOT MIX ASPHALT, ST, 9.5mm	9,447.000	TON
HOT MIX ASPHALT, ST, 12.5mm (BASE REPAIR)	3,051.000	TON
HOT MIX ASPHALT, ST, 9.5mm (LEVELING)	40.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	13,328.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
TEMPORARY TRAFFIC STRIPE (CONTINUOUS YELLOW) (PAINT)	44,187.000	LF
TEMPORARY TRAFFIC STRIPE (SKIP YELLOW) (PAINT)	5.901	MI
TEMPORARY TRAFFIC STRIPE, LEGEND (WHITE) (PAINT)	1,780.000	LF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mil)	16.895	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	5.901	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90mil)	44,187.000	LF
THERMOPLASTIC LEGEND (WHITE) (120mil)	1,780.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	785.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	50.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAP LENS)	33.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	28.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN W/SUPP. PLATE (ENCAP LENS)	1.000	EA