



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Madison

Project No. SAP-45(19)S

Road Name. Loring Road

BIDS RECEIVED: MONDAY, MAY 12, 2025 AT 10:00 AM IN THE CONFERENCE ROOM AT CANTON, MS

Project Description: 6.228 miles of RESEAL

Roadway Items:

| | | |
|--|------------|-----|
| MOBILIZATION | 1.000 | LS |
| CLEARING AND GRUBBING | 1.000 | LS |
| EXCESS EXCAVATION (FM) | 1,162.000 | CY |
| GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C) | 1,202.000 | CY |
| HOT MIX ASPHALT BASE COURSE (BB-1) | 2,301.000 | TON |
| COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS | 251.110 | SY |
| POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P | 64,765.000 | GAL |
| SEAL AGGREGATE COVER MATERIAL, SIZE 7, TYPE CRUSHED STONE | 763.000 | CY |
| SEAL AGGREGATE COVER MATERIAL, SIZE 89, TYPE CRUSHED STONE | 763.000 | CY |
| ROADWAY CONSTRUCTION SURVEYING | 1.000 | LS |
| MAINTENANCE OF TRAFFIC | 1.000 | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| 4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mils) | 12.440 | MI |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 mils) | 1.061 | MI |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mils) | 59,464.000 | LF |
| THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) (60 mils) | 686.000 | LF |
| THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) (60 mils) | 270.000 | LF |
| THERMOPLASTIC LEGEND (WHITE) (120 mils) | 392.000 | LF |
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS | 559.000 | EA |
| REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS) | 13.000 | EA |
| REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS) | 13.000 | EA |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 40.000 | EA |
| ASPHALT FOR FOG SEAL, GRADE CHPF-1 | 8,096.000 | GAL |

EROSION CONTROL ITEMS:

| | | |
|--|--------|-----|
| LOOSE RIPRAP, 100 LB. | 31.320 | TON |
| GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43 | 72.500 | SY |