



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Madison
Project No. SAP-45(20)S
Road Name. Cox Ferry Road & Spring Creek Road

BIDS RECEIVED: TUESDAY, APRIL 7, 2026 AT 10:00 AM IN THE CONFERENCE ROOM AT CANTON, MS

Project Description: 3.056 miles of RESEAL

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
EXCESS EXCAVATION (FM)	213.000	CY
CRUSHED STONE (610)	252.000	TON
HOT MIX ASPHALT, (ST) (9.5mm)	421.000	TON
HOT MIX ASPHALT, (ST) (9.5mm), LEVELING	51.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	44.440	SY
ASPHALT FOR FOG SEAL, GRADE EF-1H	4,019.000	GAL
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	32,152.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 89, TYPE CRUSHED STONE	379.000	CY
SEAL AGGREGATE COVER MATERIAL, SIZE 7, TYPE CRUSHED STONE	379.000	CY
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mils)	6.132	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 mils)	0.852	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mils)	26,631.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) (60 mils)	365.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) (60 mils)	90.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mils)	408.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	269.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	19.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	3.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	22.000	EA