



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Madison  
**Project No.** SAP-45(24)M  
**Road Name.** South Pear Orchard Road

**BIDS RECEIVED:** August 13th, 2026 at 10:00 am in the Boradroom at Canton, MS

**Project Description:** 0.312 miles of MAINTENANCE (OTHER THAN BRIDGE)

**ROADWAY ITEMS:**

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	71.000	CY
Asphalt, (ST), (19 mm)	141.000	TON
Asphalt, (ST), (9.5 mm)	878.000	TON
Asphalt, (ST), (9.5 mm), Leveling	16.000	TON
Cold Milling of Bituminous Pavement, All Depths	10,642.000	SY
Roadway Construction Surveying	1.000	LS
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Temporary Traffic Stripe, Skip White	2,607.000	LF
4"-Wide Temporary Traffic Stripe, Continuous White	2,921.000	LF
4"-Wide Temporary Traffic Stripe, Continuous Yellow	1,300.000	LF
4"-Wide Temporary Traffic Stripe, Skip Yellow	222.000	LF
Detail Traffic Stripe	4,339.000	LF
Legend	266.000	SF
6"-Wide Thermoplastic Traffic Stripe (Skip White) (90 mils)	0.494	MI
6"-Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	0.553	MI
6"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mils)	0.042	MI
6"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	1,300.000	LF
Thermoplastic Detail Stripe (6" Equivalent Length) (White) (60 mils)	1,143.000	LF
Thermoplastic Detail Stripe (6" Equivalent Length) (Yellow) (60 mils)	2,665.000	LF
Thermoplastic Legend (White) (120 mils)	708.000	LF
Thermoplastic Legend (White) (120 mils)	299.000	SF
Red-Clear Reflective High Performance Raised Markers	105.000	EA
Two-Way Yellow Reflective High Performance Raised Markers	143.000	EA