



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County	<u>Oktibbeha</u>
Project No.	<u>SAP-53(21)S</u>
Road Name.	<u>Robinson - Moor High - Crawford Road</u>

<u>BIDS RECEIVED:</u>	<u>THURSDAY, JULY 10, 2025 AT 10:00 AM IN THE SUPERVISOR'S BOARDROOM AT STARKVILLE, MS</u>
------------------------------	--

<u>Project Description:</u>	<u>6.462 miles of BASE PREPARATION & SURFACING</u>
------------------------------------	--

Roadway Items:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	1,545.000	CY
GRANULAR MATERIAL (LVM), (CLASS 3, GROUP C)	800.000	CY
SIZE 610 CRUSHED STONE BASE	2,676.000	TON
HOT MIX ASPHALT, ST, 12.5 mm, BASE REPAIR	510.000	TON
HOT MIX ASPHALT, ST, 12.5 mm, EDGE REPAIR	30.000	TON
HOT MIX ASPHALT, ST, 12.5 mm, LEVELING	715.000	TON
EMULSIFIED ASPHALT, GRADE CRS-2P	51,260.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 6, (CRUSHED STONE)	288.000	CY
SEAL AGGREGATE COVER MATERIAL, SIZE 7, (CRUSHED STONE)	973.000	CY
BLOTTER MATERIAL	139.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mil)	12.922	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 mil)	3.226	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mil)	44,582.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mil)	142.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	640.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	44.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	9.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	12.000	EA
ROADBED RECLAMATION	16,337.000	SY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	7.000	TON
COMMERCIAL FERTILIZER (13-13-13)	3.500	TON
SEEDING	3.500	AC
VEGETATIVE MATERIALS FOR MULCH	7.000	TON
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	200.000	LF
WATTLES, 20"	100.000	LF