



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Panola  
**Project No.** SAP-54(67)  
**Road Name.** MACEDONIA PARKS PLACE ROAD PART 1

**BIDS RECEIVED:** Friday, May 10, 2024 at Panola County Courthouse in Batesville, MS @ 9:00 am

**Project Description:** 0 miles of BASE, DRAIN, PAVEMENT, STRIPPING & SIGNS

**Roadway Items:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF ASPHALT (ALL DEPTHS)	367.000	SY
REMOVAL OF CONCRETE DRIVEWAY	64.000	SY
REMOVAL OF PIPE (ALL SIZES)	342.000	LF
UNCLASSIFIED EXCAVATION (F.M.)	9,913.000	CY
EXCESS EXCAVATION (F.M.)	35,531.000	CY
STRUCTURE EXCAVATION	500.000	CY
TEMORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP D)	8,433.000	CY
GRANULAR MATERIAL, (CLASS 4, GROUP C)	1,016.000	TON
PORTLAND CEMENT	4,994.000	CWT
SOIL-CEMENT-WATER MIXING (MULTIPLE PASS MIXERS)	14,757.000	SY
HOT MIX ASPHALT, (ST) (12.5 mm)	1,490.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	6,000.000	SY
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	7,231.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 56, STONE	284.000	CY
CLASS B STRUCTURAL CONCRETE	135.750	CY
REINFORCING STEEL	27,792.000	LB
15 REINFORCED CONCRETE PIPE ,CLASS III	88.000	LF
18 REINFORCED CONCRETE PIPE ,CLASS III	72.000	LF
24 REINFORCED CONCRETE PIPE ,CLASS III	184.000	LF
30 REINFORCED CONCRETE PIPE ,CLASS III	88.000	LF
36 REINFORCED CONCRETE PIPE ,CLASS III	32.000	LF
CONCRETE DRIVEWAY	55.000	SY
RIGHT-OF-WAY MARKERS (TYPE I)	49.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	2.053	MI
4 WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	0.757	MI
4 WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	4,640.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	60.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	90.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	4.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA

REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	2.000	EA
<u>EROSION CONTROL ITEMS:</u>		
COMMERCIAL FERTILIZER (13:13:13)	9.800	TON
AMMONIUM NITRATE	1.000	TON
SEEDING	9.800	AC
VEGETATIVE MATERIALS FOR MULCH	29.400	TON
SOLID SODDING	5,330.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	400.000	LF
WATTLES, 20 in	1,100.000	LF
LOOSE RIPRAP, 300 LB.	528.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43 mm	590.000	SY