



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Pearl River
Project No. SAP-55(30)M
Road Name. Roads "A" Through "C"

BIDS RECEIVED: TUESDAY, JUNE 23, 2026 AT 10:00 AM IN THE BOARDROOM AT POPLARVILLE, MS

Project Description: 4.293 miles of OVERLAY

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	41.000	CY
Crushed Stone 610	2,792.000	TON
Asphalt, ST, 19 mm	124.000	TON
Asphalt, ST, 9.5 mm	4,702.000	TON
Asphalt, ST, 9.5 mm, Leveling	1,602.000	TON
Cold Milling of Bituminous Pavement, All Depths	1,250.000	SY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 MILS)	9.067	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 MILS)	0.459	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 MILS)	45,464.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (White) (60 MILS)	1,188.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (Yellow) (90 MILS)	240.000	LF
Thermoplastic Legend (White) (120 MILS)	274.000	SF
Two-Way Clear Reflective High Performance Raised Markers	47.000	EA
Two-Way Yellow Reflective High Performance Raised Markers	371.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	16.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA