



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Pike

Project No. SAP-57(17)M

Road Name. Horace Holmes Drive and Jaguar Trail

BIDS RECEIVED: THURSDAY, OCTOBER 15, 2026 AT 11:00 AM IN THE BOARDROOM AT MAGNOLIA, MS

Project Description: 0.37 miles of WIDENING and OVERLAY

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Trees	21.000	UN
Removal of Junction Box	1.000	UN
Removal of 36" Reinforced Concrete Pipe, End Section	1.000	UN
Removal of Combination Concrete Curb and Gutter	110.000	LF
Removal of Concrete Ditch	12.000	SY
Removal of Asphalt Pavement (All Depths)	285.000	SY
Removal of Pipe (All Sizes)	84.000	LF
Unclassified Excavation (FM)	2,300.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 5)	2,000.000	CY
Granular Material (LVM), (Class 4, Group B)	350.000	CY
Crushed Stone Size 610, LVM	1,080.000	CY
Asphalt (ST) (9.5 MM)	620.000	TON
Class "B" Structural Concrete, Minor Structures	0.940	CY
18" Reinforced Concrete Pipe, Class III	30.000	LF
36" Reinforced Concrete Pipe, Class III	4.000	LF
18" Reinforced Concrete Pipe, End Section	1.000	EA
36" Reinforced Concrete Pipe, End Section	1.000	EA
Combination Concrete Curb and Gutter, Type I	200.000	LF
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Traffic Stripe (Skip White) (90 MILS)	0.049	MI
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 MILS)	0.650	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 MILS)	0.917	MI
Thermoplastic Detail Stripe (4" Equivalent Length) (White) (90 MILS)	2,665.000	LF
Thermoplastic Detail Stripe (4" Equivalent Length) (Yellow) (90 MILS)	2,637.000	LF
Thermoplastic Legend (White) (120 MILS)	135.000	LF
Thermoplastic Legend (White) (120 MILS)	307.000	SF
Two-Way Yellow Reflective High Performance Raised Markers	331.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	2.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	5.000	EA

EROSION CONTROL ITEMS:

QUANTITY UNIT

Commercial Fertilizer (13-13-13)	1.000	TON
Seeding	1.000	AC
Vegetative Materials for Mulch	2.000	TON
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	1,800.000	LF
Wattles, 20"	400.000	LF