



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Pike

Project No. SAP-57(18)M

Road Name. Magnolia-Progress Road & River Road South

BIDS RECEIVED: THURSDAY, OCTOBER 8, 2026 AT 10:00 AM IN THE BOARDROOM AT MAGNOLIA, MS

Project Description: 9.563 miles of BASE and SURFACING

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Removal of Asphalt Pavement (All Depths)	3,083.000	SY
Unclassified Excavation (FM)	1,215.000	CY
Crushed Stone Size 610, LVM	887.000	CY
Asphalt (ST), (9.5 mm)	678.000	TON
Asphalt (ST), (9.5 mm) Base Repair	1,219.000	TON
Asphalt (ST), (9.5 mm) Leveling	3,319.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mils)	19.402	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 Mils)	6.993	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	51,467.000	LF
Thermoplastic Legend (White) (120 Mils)	1,529.000	LF
Two-Way Clear Reflective High-Performance Raised Markers	452.000	EA
Two-Way Yellow Reflective High-Performance Raised Markers	720.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	35.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	33.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	1.000	EA