OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Pontotoc
Project No. SAP-58(22)M
Road Name. Roads A-D
Road "A"-Benjamin Road, Road "B"-Longview Road, Road "C"-Kings Highwa

BIDS RECEIVED: FRIDAY, JANUARY 15, 2027 AT 10:00 AM IN THE SUPERVISORS' BOARDROOM AT PONTOTOC, MS

Project Description: 8.94 miles of FOG SEAL

ROADWAY ITEMS:	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Borrow Excavation (Contractor-Furnished FME, Class 9)	3,329.000	CY
Excess Excavation (FM)	3,915.000	CY
Geotextile Fabric Stabilization (Type V) (AOS<0.43) (Non-Woven)	949.000	SY
Crushed Stone (Size 3/4" And Down) (FM)	589.000	CY
Asphalt, ST, 9.5 mm	171.000	TON
Asphalt, ST, 12.5 mm, Leveling	759.000	TON
Asphalt ForTack Coat, Grade (BC-1HT) (ETAC)	444.000	GAL
Emulsified Asphalt, Grade CRS-2	45,057.000	GAL
Coarse Aggregate Cover Material, Size 6, Crushed Stone	1,960.000	CY
Fog Seal Mixture	4,898.000	GAL
15" Reinforced Concrete Pipe, Class III	43.000	LF
18" Reinforced Concrete Pipe, Class III	128.000	LF
24" Reinforced Concrete Pipe, Class III	356.000	LF
36" Reinforced Concrete Pipe, Class III	162.000	LF
48" Reinforced Concrete Pipe, Class III	101.000	LF
60" Reinforced Concrete Pipe, Class III	116.000	LF
72" Reinforced Concrete Pipe, Class III	60.000	LF
60" Reinforced Concrete Pipe, End Section	2.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 Mils)	15.236	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 Mils)	2.005	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	64,976.000	LF
Thermoplastic Legend (White) (120 Mil)	505.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	523.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	10.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	8.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA
Loose Riprap, 300 LB.	240.000	TON

EROSION CONTROL ITEMS:	QUANTITY	UNIT
Agricultural Limestone	0.590	TON

Commercial Fertilizer (13-13-13)	0.300	TON
Ammonium Nitrate	0.080	TON
Seeding	0.300	AC
Solid Sodding	100.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	2,014.000	LF
Wattles, 20"	150.000	LF