



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Scott

Project No. SAP-62(3)M

Road Name. Roads "A" Through "B"

BIDS RECEIVED: THURSDAY, JUNE 25, 2026 AT 10:00 AM IN THE BOARDROOM AT FOREST, MS

Project Description: 4.348 miles of OVERLAY

ROADWAY ITEMS:

Mobilization	1.000	LS
Unclassified Excavation (FM)	5.000	CY
Granular Material LVM, (Class 5, Group C)	634.000	CY
Asphalt, ST, 9.5 mm (Overlay)	4,393.000	TON
Asphalt, ST, 19 mm (Base Repair)	9.000	TON
Asphalt, ST, 9.5 mm, Leveling	403.000	TON
Cold Milling Of Bituminous Pavement, All Depths	222.000	SY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (90 Mil)	8.723	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 mil)	3.063	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 Mil)	25,122.000	LF
Thermoplastic Legend (White) (120 Mil)	388.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	579.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	20.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens) (Type 3)	4.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	15.000	EA
Reflecotrized Traffic Regulatory Sign (Encapsulated Lens)	4.000	EA