



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Simpson

Project No. SAP-64(21)S

Road Name. James Berry Road

BIDS RECEIVED: TUESDAY, OCTOBER 7, 2025 AT 9:30 AM IN THE BOARDROOM AT MENDENHALL, MS

Project Description: 3.552 miles of RESEAL Base Repair, Leveling, Chip Seal, Fog Seal & Striping

ROADWAY ITEMS:

Mobilization	1.000	LS
Unclassified Excavation (FM)	691.000	CY
Asphalt, ST, 19 mm (Base Repair)	1,369.000	TON
Asphalt, ST, 12.5 mm (Edge Repair)	54.000	TON
Asphalt, ST, 9.5 mm, (Leveling)	309.000	TON
Polymerized Emulsified Asphalt, Grade CRS-2P	20,743.000	GAL
Seal Aggregate Cover Material, Size 7 (Crushed Stone)	542.000	CY
Blotter Material	70.000	CY
Fog Seal Mixture	5,658.000	GAL
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (90 Mil)	7.073	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 Mil)	2.066	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 Mil)	18,450.000	LF
Thermoplastic Legend (White) (120 Mil)	600.000	LF
Two-Way Clear Reflective High Performance Raised Markers	96.000	EA
Two-Way Yellow Reflective High Performance Raised Markers	470.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	5.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	4.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	12.000	EA