



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

<b>County</b>	Simpson
<b>Project No.</b>	SAP-64(24)S
<b>Road Name.</b>	Poplar Springs Road

**BIDS RECEIVED:** TUESDAY, OCTOBER 7, 2025 AT 10:00 AM IN THE BOARDROOM AT MENDENHALL, MS

**Project Description:** 3.319 miles of RESEAL Base Repair, Leveling, Chip Seal, Fog Seal & Striping

**ROADWAY ITEMS:**

Mobilization	1.000	LS
Unclassified Excavation (FM)	320.000	CY
Asphalt, ST, 19 mm (Base Repair)	634.000	TON
Asphalt, ST, 12.5 mm, (Edge Repair)	50.000	TON
Asphalt, ST, 9.5 mm (Leveling)	54.000	TON
Polymerized Emulsified Asphalt, Grade CRS-2P	17,993.000	GAL
Seal Aggregate Cover Material, Size 7 (Crushed Stone)	470.000	CY
Blotter Material	61.000	CY
Fog Seal Mixture	4,908.000	GAL
Maintenance of Traffic	1.000	LS
4" Wide Thermoplastic Edge Stripe (Continuous White) (90 Mil)	6.572	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 Mil)	35,048.000	LF
Thermoplastic Legend (White) (120 Mil)	780.000	LF
Two-Way Clear Reflective High-Performance Raised Markers	144.000	EA
Two-Way Yellow Reflective High-Performance Raised Markers	438.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	14.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	6.000	EA