



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Stone

Project No. SAP-66(13)M

Road Name. MAGNOLIA ROAD

BIDS RECEIVED: MONDAY, SEPTEMBER 21, 2026 AT 10:00 AM IN THE BOARDROOM AT WIGGINS, MS

Project Description: 3.811 miles of OVERLAY

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	9.000	CY
Asphalt, ST, 12.5 mm (Base Repair)	16.000	TON
Asphalt, ST, 9.5 mm (Edge Repair)	38.000	TON
Asphalt, ST, 9.5 mm, Leveling	398.000	TON
Cold Milling of Bituminous Pavement, All Depths	268.000	SY
Ultra-Thin Asphalt Pavement	2,717.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mil)	7.540	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mil)	1.192	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	33,040.000	LF
Thermoplastic Legend (White) (120 mil)	500.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	293.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	16.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	13.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	3.000	EA