



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Tippah
Project No. SAP-70(20)S
Road Name. Roads A-M

BIDS RECEIVED: THURSDAY, OCTOBER 15, 2026 AT 10:00 AM IN THE BOARDROOM AT RIPLEY, MS

Project Description: 21.084 miles of RESEAL

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	1,776.000	CY
Granular Material (LVM)(Cl. 5, Gp. "C")	446.000	CY
Crushed Stone (Size 3/4" & Down)(FM)	1,380.000	CY
Asphalt, ST, 19.0mm, Base Repair	770.000	TON
Asphalt, ST, 9.5mm, Edge Repair	315.000	TON
Asphalt, ST, 9.5mm, Leveling	1,281.000	TON
Polymerized Emulsified Asphalt, Grade CRS-2P	78,123.000	GAL
Seal Aggregate Cover Material, Size 7 (Crushed Stone or Slag)	1,800.000	CY
Blotter Material	257.000	CY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	27.320	MI
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mils)	3.792	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	120,865.000	LF
Thermoplastic Traffic Stripe (4" Equivalent Length) (Yellow) (90 mils)	575.000	LF
Thermoplastic Legend (White) (120 mils)	2,286.000	LF
Thermoplastic Legend (White) (120 mils)	63.000	SF
Two-Way Yellow Reflective High Performance Raised Markers	1,227.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	122.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	22.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	20.000	EA
Reflectorized Advance Warning Sign (Encapsulated Lens)	2.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	9.000	EA