



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

<b>County</b>	Tunica
<b>Project No.</b>	SAP-72(75)
<b>Road Name.</b>	Walnut Lake Road
	Federal Route No. 1932
<b>BIDS RECEIVED:</b>	FRIDAY, AUGUST 29, 2025 AT 10:00 AM IN THE TUNICA CO. COURTHOUSE
<b>Project Description:</b>	0.18 miles of BRIDGE and APPROACHES Construction of new bridge and approaches. Current bridge structure is closed.

**ROADWAY ITEMS:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (STA. 20+10)	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	80.000	LF
UNCLASSIFIED EXCAVATION (FM)	458.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	2,858.000	CY
CRUSHED STONE, 610	685.000	TON
HOT MIX ASPHALT, (ST) (12.5 mm)	140.000	TON
HOT MIX ASPHALT, (ST) (19 mm)	279.000	TON
24" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
GUARD RAIL, W-BEAM	125.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.360	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	0.360	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	16.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

**EROSION CONTROL ITEMS:**

HYDROSEEDING	0.660	AC
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	1,520.000	LF
WATTLES, 20"	100.000	L.F.

**BRIDGE ITEMS:**

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
24" STEEL PIPE PILING, WALL THICKNESS 0.50"	2,860.000	LF
BRIDGE CONCRETE, CLASS A	432.000	CY
60' PRESTRESSED CONCRETE BEAM TYPE III	1,493.750	LF

REINFORCEMENT	77,828.000	LB
CONCRETE RAILING	600.000	LF
LOOSE RIPRAP, 300 LB.	194.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN AOS < 0.43	236.000	SY