



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Walthall

Project No. SAP-74(64)

Road Name. RUSHINGTOWN ROAD

BIDS RECEIVED: WEDNESDAY, NOVEMBER 12, 2025 AT 10:00 AM IN THE BOARDROOM AT TYLERTOWN, MS

Project Description: 0.113 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 20+90	1.000	UN
UNCLASSIFIED EXCAVATION (PM,FM,LVM)	919.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	308.000	CY
CHANNEL EXCAVATION (FM)	685.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	251.000	CY
HOT MIX ASPHALT, ST (9.5mm)	128.000	TON
HOT MIX ASPHALT, ST (12.5mm)	256.000	TON
GUARD RAIL, W-BEAM	175.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	18.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.227	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,200.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	15.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.000	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	300.000	LF
WATTLES, 20" DIAMETER	100.000	LF
LOOSE RIPRAP, 200 LB.	402.000	TON
GEOTEXTILE FABRIC UNDER LOOSE RIPRAP, TYPE V, NONWOVEN, AOS < 0.43	410.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	920.000	LF
18 " PRE-FORMED PILE HOLES	240.000	LF

19 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD	12.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD	12.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD	6.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR, 30 DEG SKEW, RT. FWD	4.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR, 30 DEG SKEW, RT. FWD	4.000	EA
40 ' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR, 30 DEG SKEW, RT. FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	280.000	LF
36.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
36.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
36.0 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	260.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, NONWOVEN, AOS <0.43	410.000	SY