



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Warren
Project No. SAP-75(32)M
Road Name. Oak Ridge Road

BIDS RECEIVED: WEDNESDAY, MAY 6, 2026 AT 10:00 AM IN THE BOARDROOM AT VICKSBURG, MS

Project Description: 1.552 miles of OVERLAY

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Unclassified Excavation (FM)	24.000	CY
Crushed Stone (SIZE 610)	551.000	TON
Asphalt, ST, 12.5 mm (BASE REPAIRS)	46.000	TON
Asphalt, ST, 9.5 mm (OVERLAY)	1,585.000	TON
Asphalt, ST, 12.5 mm (LEVELING)	24.000	TON
Cold Milling of Bituminous Pavement, All Depths	363.000	SY
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	3.077	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	16,470.000	LF
Thermoplastic Legend (White) (120 mils)(4" Equivalent Length)	180.000	LF
Two-Way Clear Reflective High Performance Raised Markers	52.000	EA
Two-Way Yellow Reflective High Performance Raised Markers	144.000	EA