



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Wayne

Project No. SAP-77(12)M

Road Name. Winchester-Beat 2 Barn Road

BIDS RECEIVED: FRIDAY, AUGUST 29, 2025 AT 10:30 AM IN THE SUPERVISOR'S BOARDROOM AT WAYNESBORO, MS

Project Description: 0.038 miles of MAINTENANCE (OTHER THAN BRIDGE)

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	100.000	SY
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
MUCK EXCAVATION (FM)	55.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	299.000	CY
STRUCTURE EXCAVATION	260.000	CY
CRUSHED STONE (SIZE 825)	185.000	TON
HOT MIX ASPHALT, ST, 9.5mm	40.000	TON
HOT MIX ASPHALT, ST, 19 mm	24.000	TON
HOT MIX ASPHALT, ST, 9.5 mm, TRENCH WIDENING	10.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.624	CY
65" X 40" REINFORCED CONCRETE ARCH PIPE, CLASS III	96.000	LF
65" X 40" REINFORCED CONCRETE ARCH PIPE, END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.076	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	400.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	5.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13:13:13)	0.400	TON
SEEDING	0.400	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	519.000	LF
WATTLES, 12"	200.000	LF
LOOSE RIPRAP, 200 LB.	68.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43 (NON-WOVEN)	125.000	SY
EROSION CONTROL BLANKET, TYPE II	175.000	SY