



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Wayne

Project No. SAP-77(28)S

Road Name. Roads "A-E"

BIDS RECEIVED: Friday, February13, 2026 in the Boardroom at Waynsboro, MS

Project Description: 16.101 miles of RESEAL

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (F.M.)	216.000	CY
LINEAR GRADING SPECIAL	36,343.000	LF
UNCLASSIFIED EXCAVATION (SPECIAL) (L.V.M)	1,358.000	CY
CRUSHED STONE	146.000	TON
HOT MIX ASPHALT, (ST) (9.5MM) BASE REPAIR	172.000	TON
HOT MIX ASPHALT, (ST) (9.5MM), LEVELING	2,000.000	TON
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	86,362.000	GAL
SEAL AGGREGATE COVER MATERIAL, CRUSHED STONE, SIZE 7	2,132.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE COLD PLASTIC EDGE STRIPE (CONTINUOUS WHITE)	0.147	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	780.000	LF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (120 MILS)	31.735	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (120 MILS)	3.323	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MILS)	148,527.800	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	4,338.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	364.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	2,143.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	91.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	24.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE III)	32.000	EA