



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County	Pearl River
Project No.	SAP-55(15)S
Road Name.	ROADS "A" - "C"

BIDS RECEIVED:	Thursday, August 3, 2023 @ 10:00 a.m. in Boardroom at Poplarville, MS
Project Description:	12.551 miles of RESEAL

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	77.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	130.000	CY
HOT MIX ASPHALT, ST 19 MM	279.000	TON
HOT MIX ASPHALT, ST 9.5 MM, LEVELING	1809.000	TON
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	68332.000	GAL
SEAL AGGREGATE COVER MATERIAL, SIZE 7, (CRUSHED STONE OR SLAG)	1687.000	CY
BLOTTER MATERIAL	241.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	24.877	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	3.141	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	111717.000	LF
THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH) (WHITE) (60 MILS)	3145.000	LF
THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH) (YELLOW) (90 MILS)	1480.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	360.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	599.000	SF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	900.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	1280.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	105.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	23.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	24.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	4.000	EA
ASPHALT FOR FOG SEAL, GRADE CHPF-1	17896.000	GAL

