



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Lafayette
Project No. SEMP-36(2)
Road Name. West Oxford Loop Extended

BIDS RECEIVED: MONDAY, MAY 15, 2024 AT 2:00 PM IN THE LAFAYETTE COUNTY BOARDROOM AT OXFORD, MS

Project Description: 2.934 miles of GRADE DRAIN BASE & SURFACING

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	42.000	AC
REMOVAL OF 4-WAY FLASHING LIGHT ASSEMBLY	1.000	UN
REMOVAL OF CONCRETE JUNCTION BOX	1.000	UN
REMOVAL OF FENCE, ALL TYPES	553.000	LF
REMOVAL OF CONCRETE CURB AND GUTTER	1,619.000	LF
REMOVAL OF ASPHALT PAVEMENT	7,347.000	SY
REMOVAL OF CONCRETE DRIVEWAY	457.000	SY
REMOVAL OF CONCRETE PAVED DITCH	780.000	SY
REMOVAL OF CONCRETE ISLAND PAVEMENT	88.000	SY
REMOVAL OF PIPE (ALL SIZES)	811.000	LF
REMOVE AND RELAY RIPRAP	282.000	SY
UNCLASSIFIED EXCAVATION (FM)	211,436.000	CY
EXCESS EXCAVATION (FM)	45,729.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP C)	4,052.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP D)	17,643.000	CY
CRUSHED STONE	8,499.000	TON
PORTLAND CEMENT	11,778.000	CWT
SOIL-CEMENT-WATER MIXING (MULTIPLE PASS MIXERS)	49,549.000	SY
HOT MIX ASPHALT, (MT) (9.5 mm)	2,819.000	TON
HOT MIX ASPHALT, (MT) (12.5 mm)	6,419.000	TON
HOT MIX ASPHALT, (MT) (19 mm)	9,628.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	3,014.000	SY
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	24,279.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 56, STONE	1,315.000	CY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	37.877	CY
REINFORCING STEEL	2,858.000	LB
24" REINFORCED CONCRETE PIPE, CLASS III	2,480.000	LF
30" REINFORCED CONCRETE PIPE, CLASS III	616.000	LF
36" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
42" REINFORCED CONCRETE PIPE, CLASS III	128.000	LF
48" REINFORCED CONCRETE PIPE, CLASS III	200.000	LF
54" REINFORCED CONCRETE PIPE, CLASS III	96.000	LF
60" REINFORCED CONCRETE PIPE, CLASS III	96.000	LF
72" REINFORCED CONCRETE PIPE, CLASS IV	608.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	13.000	EA

30" REINFORCED CONCRETE PIPE, END SECTION	6.000	EA
42" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
48" REINFORCED CONCRETE PIPE, END SECTION	3.000	EA
54" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
60" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
72" REINFORCED CONCRETE PIPE, END SECTION	6.000	EA
CASTINGS	632.000	LB
CONCRETE DRIVEWAY	573.000	SY
CONCRETE CURB, TYPE HEADER	1,592.000	LF
COMBINATION CONCRETE CURB AND GUTTER, TYPE 1 MODIFIED	9,916.000	LF
COMBINATION CONCRETE CURB AND GUTTER, TYPE 2	1,493.000	LF
ADJUSTMENT OF SEWER MANHOLE	6.000	UN
ADJUSTMENT OF WATER VALVE	11.000	UN
CONCRETE ISLAND PAVEMENT	2,242.000	SY
RIGHT-OF-WAY MARKERS (TYPE I)	120.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
6" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP WHITE) (90 MIL)	0.192	MI
6" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	6.294	MI
6" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	0.992	MI
6" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	6.439	MI
THERMOPLASTIC DETAIL STRIPE (6" EQUIVALENT LENGTH) (WHITE) (90 MIL)	1,594.000	LF
THERMOPLASTIC DETAIL STRIPE (6" EQUIVALENT LENGTH) (YELLOW) (90 MIL)	1,518.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MI)	1,147.000	SF
RED-CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	54.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	808.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	8.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	28.000	EA
REFLECTORIZED RAILROAD CROSSING (CROSS BUCK) SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED ADVANCED WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	8.000	EA
72" TYPE I CHAIN LINK FENCE, WITH THREE-STRAND BARBED WIRE TOP GUARD	222.000	LF
GATE, 13' X 6' CHAIN LINK WITH THREE STRAND BARBED WIRE TOP GUARD	2.000	EA
LINE POSTS, 9' X 2" GALVANIZED STEEL	18.000	EA
BRACE POSTS, 10' X 2 1/2" GALVANIZED STEEL	9.000	EA
GATE POSTS, 10' X 6" GALVANIZED STEEL	2.000	EA
<u>EROSION CONTROL ITEMS:</u>		
COMMERCIAL FERTILIZER (13-13-13)	19.200	TON
AMMONIUM NITRATE	3.200	TON
SEEDING	32.000	AC
VEGETATIVE MATERIALS FOR MULCH	96.000	TON
SOLID SODDING	11,560.000	SY
PORTLAND CEMENT CONCRETE PAVED DITCH	180.910	CY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	18,085.000	LF
WATTLES, 20"	25,600.000	LF
LOOSE RIPRAP, 200 LB.	4,218.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V) (NON-WOVEN) (AOS < 0.43 mm)	5,618.000	SY
TIED CONCRETE BLOCK EROSION MAT	996.000	SY